


contact@karmicaglobal.com https://www.karmicaglobal.com PO BOX 112030, DUBAI, UNITED ARAB EMIRATES +971-524819495

Product Name :

Relief Prefabricated Foldable Medical Clinic Hospital

Product Code : KGLOB22211030



Description :

Relief Prefabricated Foldable Medical Clinic Hospital

Technical Specification :

Folding container house can be transport overall, thus can be recycled to service different projects without reconstruction. Environment protection : no construction waste, Foldable container house materials can be recycled. Nice capacity of water proof .moisture proof and heat insulation and sound insulation. Diversified Specification : Our design can be customized. The doors, windows and front and back walls can be exchanged each other. and the partition walls according to the customers' requirements. Creative folding container house practical,good space utilization and high performance.

Size: 5800*2440*2620mm

Steel Structure: Square tube and bending steel plate

Wall Panel: 50mm EPS sandwich panel /rock wool sandwich panel ,0.326/0.376/0.426/0.476mm steel sheet Wall Color: White color and optional colors

Roof: 50mm EPS sandwich panel /rock wool sandwich panel ,0.326/0.376/0.426/0.476mm steel sheet Door: 50mm EPS sandwich panel /rock wool sandwich panel ,0.326/0.376/0.426/0.476mm steel sheet with lock /optional doors

Window: Aluminum sliding door, PVC sliding door with security bar

Floor: MGO board /optional floor

Decoration Wall: Optional: PVC cladding ,WPC cladding

Electricity: Optional standard

Install Time: 2 Workers 10 mins

Wind Resistance: Wind speed?120 km/h Earthquake Resistance: Grade 8 Snow Load Capacity Of Roofing: 0.6kn/m2 Live Load Capacity Of Roofing: 0.6kn/m2 Wall Permitted Loading: 0.6kn/m2 Heat Conductivity Coefficient: 0.35kcal/m2hc